

HYC 150/300: Produktvarianten



OEM
[V1] 150-2/2

- ✓ 150kW (2x power stack)
- ✓ kleines Gehäuse
- ✓ 2x CCS Combo2 Kabel, 400A (ungekühlt)
- ✓ Kabellänge 5 m
- ✓ 2x Kabelmanagement
- ✓ Crash Sensor/Tilt Switch
- ✓ Betonfundament
- ✓ Branding

BASIC
[V2] 300-2/2
[V3] 300-4/2

✓ 300 kW (4x power stacks)

- ✓ 150 kW (2x power stacks)
- ✓ Großes Gehäuse
- ✓ 2x CCS Combo2, 400A (ungekühlt)
- ✓ Kabellänge 3,5 m
- ✓ Crash Sensor/Tilt Switch
- ✓ Betonfundament
- ✓ Branding

Premium
[V4] 300-2/2
[V5] 300-4/2

✓ 300 kW (4x power stacks)

- ✓ 150 kW (2 power stacks)
- ✓ Großes Gehäuse
- ✓ 2x CCS Combo2, 500A (gekühlt)
- ✓ Kabellänge 5,0m
- ✓ 2x Kabelmanagement
- ✓ Crash Sensor/Tilt Switch
- ✓ Betonfundament
- ✓ Branding

Public
[V6] 150-2/2
[V7] 300-4/2

✓ 300 kW (4x power stacks)
✓ Großes Gehäuse

- ✓ 150 kW (2 power stacks)
- ✓ Kleines Gehäuse
- ✓ 2x CCS Combo2, 500A (gekühlt)
- ✓ Kabellänge 5,0m
- ✓ 2x Kabelmanagement
- ✓ 2x eichrechtskonformer Zähler
- ✓ Kreditkartenterminal
- ✓ Crash Sensor/Tilt Switch
- ✓ Betonfundament
- ✓ Branding

optional

Shipping

⊕ tbd

⊕ tbd

⊕ tbd

⊕ tbd

Kabel, 5,0m

⊕ n/a

⊕ tbd

⊕ inklusive

⊕ inklusive

Ext. Not-Aus Knopf